

DEVELOPING SETS OF **LABOUR** AND WAGE RATES FOR APPROPRIATE REMUNERATION REVIEW TOWARD **IMPROVING** DELIVERY OF ELECTRICITY POWER PROJECT IN THE SOUTH EASTERN NIGERIA

ABSTRACT

In an effort to address the problem of ineffective power project delivery and poor electricity supply in the south eastern part of Nigeria especially, studies have reported that remuneration and training factors as skilled labour determinants among others are very critical for improved electricity power (EPP) delivery. In order to confirm the remuneration issue as the major factor in the area, the **this** study therefore investigates the salary and wage rates of the construction professionals and the skilled labor in the government establishments and private firms respectively. Using activity sampling technique, the masonry (block laying) and carpentry trades in the power sector of the south east were investigated. Findings **have shown** that the average non productive and active times of **both masonry and carpentry trades** are at an average of 25 - 37.20% and 62.5 - 75% accordingly and at an average of 18.80 - 31.20% and 68.80 - 81.20% respectively. The This study also has **also proves** that standard times and standard outputs of masonry and carpentry trades respectively stand at 1.37hr/m² and 0.75m²/hr for masonry trades, and 0.85hr/m² and 1.19m²/hr for carpentry trade. Consequently, the labor rates of masonry and carpentry trades are estimated at 6m² and 9.52m² respectively. In an effort to compare the labor rate of the skilled workers in the EPP with those in some major construction firms and civil service, it was discovered that labor rates of workers in EPP are much lesser than the others; likewise the wage rates respectively. Although the labor rate of the skilled labor in EPP are lesser than those in the **other commission** of services, **the wage rates of the respective trades in EPP are non proportionally quite lesser than the wage rates in the other areas of employment;** hence the ratio of the wage rate to labor rates in EPP are significantly lesser than the ratios in the other areas

especially, the construction firms in the study area. It was therefore recommended to establish **This study recommends an establishment of a data base** framework in the power sector for improved remuneration of the skilled labor that incorporates need based and certified training programme, towards effective delivery of EPP in the south east and Nigeria in general.

Key Words: Electricity Power Project Delivery, Skilled Construction Labor, Remuneration, Activity Sampling, Labor Constants, and Wage Rates.

INTRODUCTION

Electricity power project delivery has remained a major problem in the **South-Eastern States (S.E.S.) of Nigeria, and Nigeria as a country** in general. **Okafor, (2013)** In his contributions confirmed that size of skilled workforce needed to keep Nigeria's electric power system running is huge; and that about 17,441 skilled workers are needed to work in the power sector as the electricity market is expected to expand to about 40,000 megawatts (MW) capacity by 2020. It is however, difficult to have electricity supply at near peak presently. Mohammed, (2007) contends that beside other challenges in the power sector, there is shortage of skilled manpower to maintain the power generating plants. Since shortage and low productivity of skilled manpower has been noted as a major problem in the delivery of the electricity power project and services/maintenance of the generating plants in Nigeria, effort are made to determine the socio-economic characteristics of the skilled labor affecting the power project and the plants (Ikechukwu, 2019). He therefore concluded that remuneration and training determinants among other socio-economic characteristics of the skilled labor are very prominent in their contribution to effective delivery of EPP in the south eastern Nigeria.

In assessing the average performances of the various trades in the industry, average productivity and wage rate of the skilled labor in the industry are estimated with the proper knowledge of work study in a given environment. This usually involves method study work measurement of the job task containing the targeted work activities. In the process of activity sampling, a large number of observations are made of the workers over an extended period of time. The observations are at random times during the period of study to ensure statistical accuracy. The period must be the representative of the types of activities performed by the subjects. It is the statistical technique used in determining the proportion of time spent by workers in various defined categories of activity (Diogu, 2017). It is primarily used in the determination of the standard labor constants for a manual task. Similar techniques for this task are time study, standard data, and predetermined motion time systems.

In evaluating the amount of time spent on various categories of work by the trade workers in their assigned tasks, work sampling helps to identify any trend affecting labor productivity. Based on this fact, work sampling provides framework with which a construction project would be completed on time and within budget. Hence, relationship between productivity rate and work sampling are usually predicted (insert reference).

Labor is one of the basic requirements in construction work; and labor productivity usually relates manpower in terms of labor cost to the quantity of output produced. Thomas (2014), in his contribution titled “Energy Industry Struggling with Labor Shortage” said that the Energy Industry in the United States (US) is facing a skilled manpower shortage which risks billions of dollars in energy investment and new technologies.

Furthermore, he contends that the average age of today's worker is 46, with 60 percent planning to retire at the next ten years. At the same time, the demand for energy is increasing every day. The aging trend of the workforce without commensurate new talents and skills replacing them poses the largest threat to the energy sector today. This has become so large and complex for any stakeholder or group to solve.

The National Power Training Institute of Nigeria (NAPTIN, 2013) reveals that there are 8,440 skilled workers generally running Nigeria Power System. It said that it has a yearly average intake of 250 students, which is not quite enough to move the projected 40,000 MW by 2020. This shows that there is a large gap left. It is therefore agreed that lack of skilled manpower in the defunct PHCN is one of the major problems that plagued the development of the Nigerian Power Sector (Diogu, 2017)

Appropriate labor output with suitable wage rate leads to effective production performance through efficient labor production and stable supply of competent labor. Since labor rate needs to be estimated based on the production capacity of the workers, the constants of labor for establishing the cost of labor in the item of works contained in the bill of quantities therefore, need not be guessed or imagined. It is then, difficult to draw reliable conclusions or accurate cost estimation without any available baseline standards. The standards (labor constants) are guided by standard supply of labor, effective labor production and activities sampling. These standards are mainly the standard time (S_t) and standard output (S_{op}) for a specified work period in a given construction environment (insert reference).

Achieving an increase and sustainable labor productivity requires detailed studies of the labor organization and cost. Determination of the optimal labor force in any organization ~~of labor~~ becomes important in order to identify the least possible composition of a work team necessary to accomplish a given project at minimal labor cost and within a time frame (insert reference).

Thomas, (1984), declared that, on the basis of a 10 week crew based sampling study, ~~found that~~ the correlation coefficient between direct work portion of work sampling and ratio of earned to actual man-hours would increase, if the definition of direct work was restricted, (Dasgupta et al, 2014). The relationship between work sampling values and productivity measurement were investigated in their work (whose work???), with an objective of using work sampling as a surrogate productivity measure. It is concluded therefore that the work sampling could be used as a reliable estimator of construction productivity, provided the definition of direct work was narrowly defined.

Dasgupta, (2014) also cited in their work that Liou, et al (1986), used forty five work sampling data point, that were collected from eleven nuclear power projects and 4 fossil fuel power projects to support the existence of relationship between work sampling and productivity rate by statistical analysis. It was established that work sampling was a good labor productivity indicator and also a valuable predictor in productivity projection model.

Thus, to achieve this, the following labor constants (rates) are necessary.

- i. Standard time (S_t) – The normal time frame necessary for the production of a unit quality work. The unit is man – hour/m²;
- ii. Standard output (S_{op}) – The quantity of good quality work completed in a unit time frame by a tradesman or gang of tradesmen. The unit of measurement is quantity of work - hour e.g. M³/m-h;
- iii. Labour output (L_o) – Output rate on daily basis;
- iv. Labor Required (L_r) – Required labor for a required quantity of work in a day and;
- v. Time frame (T) – Contract time frame from commencement to the completion of work or a given quantity of work, using $\sum Pt$ (number of workmen)

The relationships between these constants are presented as follows:

$$S_t = t/q, \quad S_{op} = t/S_t, \quad L_o = S_{op} \cdot t, \quad L_r = Q/S_{op} \cdot t$$

Where,

q is quantity of quality work produced,

t - duration of a work per day (in Nigeria, t = 8 hours), and

Q - total quantity of good work to be accomplished.

RESEARCH METHOD AND MATERIALS

A field survey design approach was adopted in the original research study the help of questionnaires and activity sampling. A group focus discussion for sampling process helped to form strong base for reasoning and decision making on different work trades and their conditions/categories. Thus, data obtained by way of activity sampling were used to establish labor constants and labor rate of the respective trades of defined conditions. The duration of direct observation for the sampling sequentially lasted 2 weeks, in the

respective work trades. The standards eight (8) working hours in a day were maintained. Recreation, odd period and tradesman work efficiency rate in each of the days were estimated with percentage on a daily basis.

Based on the observations carried out on the masons and carpenters working at the various sites of the study, the active (direct and supportive) and non-active (non-productive) production stages in the construction processes were identified.

Number of Observations for Sampling of the Activities

The magnitude of observations required to determine holistically the proportion of productive and unproductive times of the respective skilled construction work forces for EPP in the study area is estimated using the following expression:

$$N_{ob} = \frac{k^2 p (1-p)}{L^2} \quad \text{--- --- --- --- --- --- ---} \quad \text{(Equ1)}$$

Where,

N_{ob} is the required numbers of the observations on the activities for establishing realistic performance ratings,

K = value obtained from Fisher statistical table. ($K = 2$),

L = limit of accuracy at 0.1 significance Level,

P = the percentage of activity observed, at 50%

Thus, according to Equation Equ 1, N_{ob} is calculated as:

$$N_{ob} = \frac{2^2 \times 0.5 (1- 0.5)}{0.1^2} = \frac{4 \times (0.5 \times 0.5)}{0.01} = 100$$

Therefore, N_{ob} is 100

DATA PRESENTATION, ANALYSES AND DISCUSSION OF FINDINGS

In each of the activities sampled in the study in every given time, note were taken of the cumulative time involved in the active and non active states of the respective workmen ~~in~~ on the job. At the maximum of every 30 minutes interval, this observation would always be carried out for average assessment in the study for mason and carpentry trades respectively.

It means that observations were taken in every half hour of the 8 working hours per day.

A total of 288 observations were taken at the three sites of the respective states in more than one week. Every half hour observations were made in 8 hours in a day at each of the respective project site with average gang of tradesman and helper, for the respective trades. Out of the 288 observations made for block laying activity, 198, 216, 180, 180 and 216 observations were made as active in the respective states; while 90, 72, 108, 108 and 72 observations were non-productive ones respectively, for the average working conditions of block layers in the three project sites in the states respectively. The respective observations therefore, are calculated in percentages in the following forms.

Masonry (Block Laying) Work Activity in the South East.

i. Abia State Sites

$$\text{Percentage of Non-productive time} = \frac{90}{288} \times \frac{100}{1} = 31\%$$

$$\text{Percentage of Active time} = \frac{198}{288} \times \frac{100}{1} = 69\%$$

Using the same approach, the non productive and active times of the block laying activities in other states are **were** calculated as presented in Table 1.

Table 1. The Non Productive and Active Times of the Block Laying Activities

S/N	Work Conditions	Abia	Anambra	Ebonyi	Enugu	Imo	Remark
1	Non Productive Time	31	25	37.5	37.5	25	
2	Active Time	69	75	62.5	62.5	75	

Source: Author's Field Work, (2017)

**Standard Time and Output on Block Laying Works in Abia State Sites
Average set of a Mason and Helper**

Average observed time (OT): 8 hours

Average output: 10m²/day

Therefore, output per hour = $\frac{10}{8\text{hours}} = 1.25\text{m}^2/\text{hr}$

Basic time: OT + Recreation + Allowance for odds

Basic time: OT + 17%

Basic time: 8 + 1.36 = 9.36 hours (for 10m²)

Standard work performance rates 100%

Thus, based on the labor performances, the estimated rate is 69%

Therefore output = $\frac{69}{100} \times \frac{10}{1} = 6.90\text{m}^2/\text{day}$

Since standard working hour/day is 8hours, and 6.90m² measure of output is delivered in 9.36 hours;

In 8 hours therefore, output = $\frac{8}{9.36} \times \frac{6.90}{1} = 5.90\text{m}^2/\text{day}$ (labor rate)

Standard Time

For 1m² = $8/5.90\text{m}^2 = 1.36\text{hrs}$

Standard Output

$$\text{For 1 hour} = \frac{5.90\text{m}^2}{8 \text{ hrs}} = 0.74\text{m}^2/\text{hr}$$

Finally, the net standard time and output of building projects are **were** calculated as follows:

Note that net standard time of masonry work is therefore **taking taken** as the arithmetic mean of the results obtained from the various sites of the respective state sampled.

$$\begin{aligned} \text{Thus, Net } S_t &= \frac{1.36 + 1.20 + 1.57 + 1.57 + 1.14 \text{ hrs}}{5} \\ &= \frac{6.84\text{hrs}}{5} = 1.37\text{hrs/m}^2 = 82.20 \text{ mins/m}^2 \end{aligned}$$

ii) In the same way net standard output (S_{op}) in the study area is **was** thus calculated as follows:

$$\begin{aligned} \text{Net } S_{op} &= \frac{0.74 + 0.83 + 0.64 + 0.64 + 0.88\text{m}^2}{5} \\ &= \frac{3.73\text{m}^2}{5} = 0.75\text{m}^2/\text{hr} \end{aligned}$$

iii) Thus, Labor Rate which is expressed as the product of Standard Output (S_{op}) and standard day work duration (8hrs) is **was** therefore, calculated as follows

$$L_r = 0.75\text{m}^2/\text{hr} \times 8\text{hrs} = 6\text{m}^2/\text{day}$$

Carpentry Work Activity in the South East.

For the carpentry work trade, the average working conditions of the tradesmen sampled in the respective project **sites show** that out of the 288 observations in each state, the active observations made are **were** 216, 198, 234, 198 and 216 observations respectively, while the non productive

observations made are were 72, 90, 54, 90 and 72 observations in the three project sites of each of the state respectively. They are were calculated in percentages in the following forms.

Standard Time and Output on Carpentry Works in Abia State Sites

$$\text{Percentage of Non-productive time} = \frac{72}{288} \times \frac{100}{1} = 25\%$$

$$\text{Percentage of Active time} = \frac{216}{288} \times \frac{100}{1} = 75\%$$

Using the same approach, the non productive and active times of the carpentry activities in other states are were calculated as presented in Table 2.

Table 2. The Non Productive and Active Times of the Carpentry Activities

S/N	Work Conditions	Abia	Anambra	Ebonyi	Enugu	Imo	Remark
1	Non Productive Time	25	31.20	18.80	31.20	25	
2	Active Time	75	68.80	81.20	68.80	75	

Source: Author's Field Work, (2017)

Abia State Sites:

Average observed time (OT): 8 hours

Output: 14.2m²

$$\text{Therefore, output per hour} = \frac{14.2\text{m}^2}{8} = 1.78\text{m}^2/\text{hr}$$

Basic time: OT + Recreation + Allowance for odds

Basic time: OT + 16% (OT)

Basic time: 8 hours+ 1.28 = 9.28 hours (for 14.2m²)

Standard quality work has rating of 100%

Thus, base on the labor performances the estimated rate is 75%

$$\text{Output} = \frac{75}{100} \times \frac{14.20}{1} = 10.65\text{m}^2/\text{day}$$

Hence, 10.65m^2 is for 9.28 hours

Since standard work hour/day is 8hours:

$$8 \text{ hours therefore is} = \frac{8}{9.28} \times \frac{10.65}{1} = 9.18\text{m}^2/\text{day} \text{ (labor rate)}$$

Standard time

$$\text{For } 1\text{m}^2 = 8/9.18\text{m}^2 = 0.87\text{hrs}/\text{m}^2 = 52\text{mins}/\text{m}^2$$

Standard output

$$\text{For 1 hour} = \frac{9.18\text{m}^2}{8 \text{ hrs}} = 1.15\text{m}^2/\text{hr.}$$

For Average Standard time and output of the carpentry work in the study area consisting of the 5 respective state sites, the labor constants are **were** obtained as follows:

Net Standard time (S_t) for the Carpentry trade work

$$S_t = \frac{0.87 + 0.92 + 0.74 + 0.97 + 0.77 \text{ hrs}/\text{m}^2}{5}$$

$$\text{Thus, } S_t = \frac{4.30 \text{ hrs}/\text{m}^2}{5} = 0.85 \text{ hr}/\text{m}^2 = 51 \text{ mins}/\text{m}^2$$

Net Standard output (S_{op}) for the carpentry trade work

$$S_{op} = \frac{1.15 + 1.10 + 1.36 + 1.03 + 1.29 \text{ m}^2/\text{hr}}{5}$$

$$\text{Thus, } S_{op} = \frac{5.93 \text{ m}^2/\text{hr}}{5} = 1.19\text{m}^2/\text{hr}$$

Thus, labor rate which is expressed as the product of Standard Output S_{op} and standard day work duration (8 hrs) is **was** therefore, calculated as follows:

$$L_r = 1.19 \text{ m}^2/\text{hr} \times 8 \text{ hrs} = 9.52\text{m}^2/\text{day}$$

Appropriate labor rates of different study areas according to Ikechukwu, et al (2015) and Diogu, (2017) had therefore been established to help form the bases for improved productivity of labor, as well as the regulations of rates of productions in the various trades in the industry. The labor constants of some of the skilled construction workforces as presented in Table 3 shows the labor rates of the masonry (block laying) and carpentry trades respectively obtained in the various Construction projects, Civil service and the EPP in the study as follows.

Table 3. Labor Rates of the Skilled Construction Workforces in the Various Construction Projects and the EPP

S/N	TRADES	CONSTRUCTION PROJECTS											
		Owerri Metropolis			Multi-Trust Construction			Geo-skill Engineering			EPP		
		Labor Output	S_t	S_{op}	Labor Output	S_t	S_{op}	Labor Output	S_t	S_{op}	Labor Output	S_t	S_{op}
1	Block Laying	7.70	1.10	0.96	9.12	0.90	1.14	8.80	1	1.1	6	1.37	0.75
2	Carpentry	12.30	0.65	1.54	12.32	0.65	1.54	12.80	0.63	1.6	9.52	0.85	1.19

Source: Adapted from Ikechukwu, (2015), and Author's Field Work, (2017).

Wage Rate Determination: A satisfactory wages scheme is characterized with high productivity level, and low labor turnover. Wage means of remuneration for the skilled construction workers within the **south-eastern**

geopolitical region of Nigeria ranges between three thousand naira (N3000) to four thousand naira (N4000) per day in the current economic situation of the nation.

For the reason of wage rate analysis, remuneration (salary) of skilled construction workforces in the civil service and various EPP commissions in particular were interpreted into wages on the basis of five (5) working days in a week. Presented in Tables 4 are the salary structure of skilled construction workforces in civil service and TCN/DISCOS annually, with their corresponding wage rates per day.

Table 4: The Wage/Salary Structure of Skilled Construction Workforce in Civil Service and TCN/DISCOS

S/N	Grade Level (GL)	Civil Service (#)		TCN/DISCOS (#)		Remarks
		Salary/yr	Wage/day	Salary/yr	Wage/day	
1	GL 01	226,800	945	144,180	601	
2	GL 02	231,269	964	147,024	613	
3	GL 03	235,738	982	150,804	628	
4	GL 04	240,207	1001	168,012	700	
5	GL 05	244,677	1020	190,764	795	
6	GL 06	249,146	1038	232,128	967	

Source: Author's Field Work, (2017)

Thus, the skilled construction workers in the civil services and TCN/DISCOS commissions are commonly within the grade cadres of GL 04 to GL 06. Hence, the average wages of the civil service and TCN/DISCOS workers, as well as the average wage rate of skilled

construction workers in the study area per day are **were** calculated as **to be** ₦1,020, ₦821 and ₦3,500 respectively.

SUMMARY OF THE MAJOR FINDINGS

Information obtained through the activity sampling shows that the skilled workers have not been productive in general especially, **when compared with the productivities of the workers in the construction firms within the study area (Table 3)**. Although the active working periods observed in the activity sampling ranges from 62.50% to the maximum of 81.20% on average, it is seen that carpentry tradesmen utilize more of their working hours than the masonry tradesmen. With these situations, decision making during analysis for improved labor performance would be reliable for effective delivery of EPP in the study area. Thus, the labor constants established have average of 1.37hrs/m² and 0.75m²/hr for standard time and standard output respectively for masonry trade, while the average of 0.85hr/m² and 1.19m²/hr for standard time and standard output respectively are for carpentry trade.

The wage rates of the respective skilled workforce in the EPP pose the worst scenario; where their respective remunerations on wage analysis are about 25% value of their counterpart in the surrounding private construction firms (Table 4). With the existing poor wage scheme in EPP delivery management, results show that the average labor rates of the block laying and carpentry trades stand as low as 6m²/day and 9.52m²/day respectively.

Although the remuneration of the skilled workers in the civil service and TCN/DISCOS commissions are characterized with life accruing benefits like; job security, gratuity and pension, the differences in their remuneration and that of the skilled workers in the construction firms are alarming; to the expense of the workers in civil services, and in the EPP especially. Thus, considering the comparison of the ratio of wage-labor rates of the major private construction firms with that of the TCN/DISCO in the area which stand at #410/m² and #281/m² for block laying and carpentry trades respectively, and the corresponding #137/m² and #87/m² for block laying and carpentry trades respectively, the workers of the TCN/DISCO employment are quite underpaid compared to their counterparts in the private construction firms; hence the implication of the poor wage rate outweighs the attached benefits of the civil service and EPP workers respectively.

This condition explains the reason the skilled labor rates of the skilled workers in the civil services and the TCN/DISCOS workers are relatively less than the labor rates in the construction firms around. It therefore supports the belief that remuneration issue is very critical in an effort to improve on the delivery of EPP. If the wages/salaries of the skilled labor in TCN/DISCOS are very well improved on, their labor outputs will automatically be improved at that same rate when they are properly trained, retrained and monitored.

CONCLUSION

In conclusion, the study explains therefore the reason the model analyses on relationships between the labor determinants and effective EPP delivery

according to Diogu, (2017) pointed at remuneration as the most significant influential factor for improved productivity in the power sector, as well as the cause for poor production drive that results to low output rate of the workers in the study; hence supporting the belief that wage rate affects workers productivity in EPP. Besides, as the study explains that the wage rate of an EEDC/TCN staff shows a variance when compared with its equivalent in the government civil service, and a more significant variance when compared with those in the private construction firms, skilled workers in the power project are underpaid in their services. This ofcourse would make the skilled workforce put less effort to work. They either take money from a consumer before rectifying a reported fault or it is not attended to at all for a long time because of poor condition of work. To address this problem sustainably, a framework should be put in place to strategically improve the performance of the skilled labor for effective EPP delivery. It provides therefore a skilled labor with a minimum basic qualification. When the tradesman is employed with the appropriately enhanced wage rate in the power sector, he undergoes a training development programme of National Vocational Qualification Framework (NVQF) to be certified by an approved verifier of the Nigeria Institute of Builders (NIOB) under the authority of the National Board for Technical Education (NBTE). As a certified skilled labor, one will be able to have a significant mark up in production that is commensurate to his services for both the block laying and carpentry trades respectively.

REFERENCES

Dasgupta, A. and Koshy, V. 2014. Investigation of Relationship between Results of Work Sampling and Productivity Measurement: Department of Civil Engineering, Indian Institute of Technology, Madras India. Email: anupamdasgupta88@gmail.com Mumbai India.

Ikechukwu, U. F. and Anekwe, M.C. 2015. Establishing Appropriate Labour Output Rate for Increased Site work Productivity of Building Projects in Owerri Metropolis, Imo State. An International Journal of Economic Development Research and Investment: ICIDR. Akwa-Ibom, Nigeria. 7(2), 51-62.

Ikechukwu, U. F. 2019. An Assessment of the Implications of the Major Socio-Economic Characteristics of the Construction Skilled Labor on Effective Delivery of Electricity Power Project in the South Eastern Nigeria. Current Journal of Applied Science and Technology. CJASST/49677. SCIENCEDOMAIN International, UK.

Liou, F.S. and Borcheding J.D. 1986. Work Sampling Can Predict Unit Rate Productivity: Journal of Construction Engineering and Management; 11(2), 90 – 102.

Mohammed, K. B. 2007. Why Electricity Generation in Nigeria is in a Sorry Condition: Daily Times Newspaper; December 9, 2007; Ile-Ife Press.

National Power Training Institute of Nigeria, (NAPTIN). 2013. The Training of Skilled Manpower for the Country Electricity Power Industry. Nigeria.

Okafor, C. (2013). Plugging of Manpower Delivery in the Power Sector, PHCN Newsletter, November 13. Diogu, U. R. 2017. Enhancing the Production Performance of Skilled Construction Labor for Effective Delivery of Electricity Power Projects (EPP) in the South East States of Nigeria. A Successful PhD Dissertation in Construction Management Presented in the School of Post-graduate Studies, Imo State University, Owerri. Nigeria.

UNDER PEER REVIEW